



**NSW
Resources
Regulator**

FWP0001459

NORTH EAST MINE FORWARD PROGRAM

Monday 1 July 2024 to Wednesday 30 June 2027

Summary

DETAIL

Mine	North East Mine
Reference	FWP0001459
Forward program commencement date	Monday 1 July 2024
Forward program end date	Wednesday 30 June 2027
Forward program revision (if applicable)	
Contact	Mike Fake
Mining leases	ML 1818 (1992), ML 1383 (1992)
Project location	TRITTON RESOURCES PTY LTD
Date of submission	Friday 30 August 2024

Important

The department may make the information in your program and any supporting information available for inspection by members of the public, including by publication on its website or by displaying the information at any of its offices. If you consider any part of your program to be confidential, please communicate this to the department via the message function on this submission within the NSW Resources Regulator Portal.

Three-year forecast – surface disturbance activities

Project description

For the purposes of this report, North East Mine (the Mine) refers to both the North East Copper Mine (NECM) (ML1383) and the Avoca Tank Project (ATP)(ML1818). It is noted that the previous FWP referred only to NECM. The Mine is located approximately 6km northwest of the village of Girilambone within the Bogan LGA in central west NSW. The Mine is owned and operated by Tritton Resources Pty Ltd (the “Company”), a wholly owned subsidiary of Aeris Resources Limited. DA 6/95 9 (NECM) was issued by Bogan Shire Council in '95 and does not contain an expiry date. Open cut mining commenced in '96. Open cut mining was completed by '00 and from '07, mining was recommenced using underground extraction methods with mined ore transported to the Tritton Copper Mine for processing. The Mine remains on care and maintenance, however the Hartman’s Pit and internal roads are currently used for access to the ATP. DA10/2015/004/002 was granted 15 Sep '16. ATP commenced Oct 21 and production began q423.

Description of surface disturbance activities

Exploration activities

Nil surface exploration with the Mine Site is anticipated to occur within the Reporting Period. Underground exploration will continue.

Construction activities

Construction of a concrete batch plant within an existing disturbance area / current mine infrastructure area above the Hartmans Open Cut Pit. Other than removal of plant and concrete footings, removal of the concrete batching plant at the end of mining is not expected to present any risk to rehabilitation of the Mine.

Mining schedule

Mining development method and sequencing and general mine features.

No significant changes to surface operations are anticipated to occur. Mining will only occur within the underground mines at ATP and potentially NECM if required. Mining at ATP consists of long-hole open stope methods. Within NECM, 'salvage' mining of remnant pillars left following previous underground mining campaigns may occur to maintain ore feed at the TCM processing Plant, if required.

Areas identified for emplacements, the sequencing of emplacements, construction, and management.

Emplacement within surface WREs was completed in the mid 2000's. Backfilling of final voids within the NECM with NAF waste rock may continue as required to achieve long-term stability. Remediation of areas of failed vegetation on the WREs may be undertaken follow result of ongoing investigations (i.e material characterisation)

Processing infrastructure activities and the location of tailings facilities and schedule for emplacement.

No processing occurs within the Mine Site. It should be noted that all Reject Material and Product identified under Key Production Milestones is generated at Tritton Copper Mine.

Waste disposal and materials handling operations.

All waste generated on site is transferred to either the MCM or TCM sites for temporary storage / handing / treatment prior to lawful disposal. More information is presented in the reporting for TCM.

Key production milestones

MATERIAL	UNIT	YEAR 1	YEAR 2	YEAR 3
Stripped topsoil <small>(if applicable)</small>	(m ³)	0	0	0
Rock/overburden	(m ³)	64,300	5,300	160
Ore	(Mt)	0.47	0.34	0.38
Reject material¹	(Mt)	0.43	0.32	0.35
Product	(Mt)	0.01	0.01	0.01

¹ This includes coarse rejects, tailings and any other wastes resulting from beneficiation.

Three-year rehabilitation forecast

Rehabilitation planning schedule

Rehabilitation planning schedule

- Post Closure Water Management Study (Aim complete 25/26) - relies on current Site Wide Water Balance Model. Anticipated that the results will inform post closure water management / licencing requirements. - Development of program for seed collection/storage and investigation into propagation methods (e.g. on-site nursery or contractor) (Aim complete 25/26)

Stakeholder consultation

Ongoing general consultation as part of CCC meetings.

Rehabilitation studies, risk assessments and/or design work

Year 1 - Geotech Stability Assessment and Surface Water Management Assessment in response to NCTE0014657 (complete 24/25) - LEM (complete 24/25) currently in preparation for MCM and NECM WREs. Investigation into additional data (e.g. LiDAR) for refinement of models. Once model parameters are further developed then will be applied to TCM. - Site Wide Water Balance Model (all sites) (Complete 24/25) - Post Closure Water Management Study (Aim complete 25/26) - relies on current Site Wide Water Balance Model - Hydromulch Trials (Site to be confirmed) (Ongoing) Year 2 - Biennial Rehabilitation Monitoring Campaign (25/26) - Post Closure Water Management Study (Complete 25/26) - relies on current Site Wide Water Balance Model

Rehabilitation research and trials

RRT NUMBER	PROJECT/TRIAL NAME	OBJECTIVE OF TRIAL/PROJECT	METHODOLOGY	EXPECTED DATE OF COMPLETION	STATUS
------------	--------------------	----------------------------	-------------	-----------------------------	--------

FWP0001
459

Rehabilitation maintenance and corrective actions

Remediation of failed vegetation development on the NECM WREs may commence during the reporting period.

Rehabilitation schedule

Mining at ATP is approved to occur for approximately 4 years from commencement of mining operations (q423), or 31 December 2027. Based on the above, no significant surface disturbance or rehabilitation within the Mine Site is anticipated to occur during the reporting period. Decommissioning of surface infrastructure within the ATP Mine Site is anticipated to commence during FY27/28.

Subsidence remediation for underground operations

Nil.

Progressive mining and rehabilitation statistics

Three-yearly forecast cumulative disturbance and rehabilitation progression

FORECAST	UNIT	YEAR 1	YEAR 2	YEAR 3
A Total surface disturbance footprint	(ha)	150.67	150.67	150.67
B Total active disturbance	(ha)	49.41	49.41	49.41
P Total new area of land proposed for active rehabilitation	(ha)	0	0	0

Rehabilitation key performance indicators (KPIs)

FORECAST	UNIT	YEAR 1	YEAR 2	YEAR 3
O Total new active disturbance area	(ha)			
P Total new area of land proposed for active rehabilitation during the reporting period	(ha)			
Q Annual rehabilitation to disturbance ratio				

Attachment 1 – Reporting Definitions

REPORTING CATEGORY	DEFINITION
<p>A Total disturbance footprint – surface disturbance</p>	<p>All areas within a mining lease that either have at some point in time or continue to pose a rehabilitation liability due to surface disturbance activities.</p> <p>The total disturbance footprint is the sum of the total active disturbance, decommissioning, landform establishment, growth medium development, ecosystem and land use establishment, ecosystem and land use development and rehabilitation completion (see definitions below).</p> <p>Underground mining operations should not include the footprint of underground mining areas/subsidence management areas in the total disturbance footprint.</p>
<p>B Total active disturbance</p>	<p>Includes on-lease exploration areas, stripped areas ahead of mining, infrastructure areas, water management infrastructure, sewage treatment facilities, topsoil stockpile areas, access tracks and haul roads, active mining areas, waste rock emplacements (active/unshaped/in or out-of-pit), tailings dams (active/unshaped/uncapped) and temporary stabilised areas (e.g. areas sown with temporary cover crops for dust mitigation and temporary rehabilitation).</p>
<p>C Rehabilitation – land preparation</p>	<p>Includes the sum of all disturbed land within a mining lease that have commenced any, or all, of the following phases of rehabilitation – decommissioning, landform establishment and growth medium development.</p> <p>Refer to the glossary of terms in this document for the definition of these phases of rehabilitation.</p>
<p>D Ecosystem and land use establishment</p>	<p>Includes the area which has been seeded/planted with the target vegetation species for the intended final land use. However, vegetation has not matured to a stage where it can be demonstrated that it will be sustainable for the long term and or require only a maintenance regime consistent with target reference/analogue sites.</p> <p>Typically, rehabilitation areas would be in this phase for at least two years (and usually more) before rehabilitation can be classified as being in the ecosystem and land use development phase. This phase does not apply to infrastructure areas that are being retained as part of final land use for the site.</p>

REPORTING CATEGORY	DEFINITION
O	The area of any new active disturbance that will be created during the next three years, as defined under definition A1 (definition A1 Table 5).
P	The sum of any new rehabilitation to be commenced in the next three years. These areas may be in the phases “Rehabilitation - Land Preparation” or the “Ecosystem & Land Use Establishment” (definitions C & D in Table 5).
Q	The rehabilitation to disturbance ratio (S / R) indicates how many hectares of new rehabilitation are undertaken for each hectare of land disturbed during the three years. A ratio of 1/1 indicates that the area of new rehabilitation and disturbance in that period are the same.

Attachment 2 – Definitions

WORD	DEFINITION
Active	In the context of rehabilitation, land associated with mining domains is considered ‘active’ for the period following disturbance until the commencement of rehabilitation.
Active mining phase of rehabilitation	In the context of rehabilitation, the active mining phase of rehabilitation constitutes the rehabilitation activities undertaken during mining operations such as salvaging and managing soil resources, salvaging habitat resources, and native seed collection. This phase also includes management actions taken during operations to manage risks to rehabilitation and enhance rehabilitation outcomes such as selective handling of waste rock and management of tailings emplacements.
Analogue site	In the context of rehabilitation, an analogue site is a ‘reference site’ that represents an example of the defining characteristics (such as vegetation composition and structure or agricultural productivity) of the final land use. Characteristics of analogue sites can be assessed to develop the rehabilitation objectives and completion criteria for final land use domains.
Annual rehabilitation report and forward program	As described in the Mining Regulation 2016.
Annual reporting period	As defined in the Mining Regulation 2016.
Closure	A whole-of-mine-life process, which typically culminates in the relinquishment of the mining lease. It includes decommissioning and rehabilitation to achieve the approved final land use(s).
Decommissioning	The process of removing mining infrastructure and removing contaminants and hazardous materials.
Decommissioning Phase of Rehabilitation	Activities associated with the removal of mining infrastructure and removal and/or remediation of contaminants and hazardous materials. In the context of the rehabilitation management plan this phase of rehabilitation may also include studies and assessments associated with decommissioning and demolition of infrastructure or works carried out to make safe or ‘fit for purpose’ built infrastructure to be retained for future use(s) following lease relinquishment.

WORD	DEFINITION
Department	The Department of Regional NSW.
Disturbance	See Surface Disturbance.
Disturbance area	<p>An area that has been disturbed and that requires rehabilitation.</p> <p>This may include areas such as on-licence exploration areas, stripped areas ahead of mining, infrastructure areas, water management infrastructure, sewage treatment facilities, topsoil stockpile areas, access tracks and haul roads, active mining areas, waste emplacements (active/unshaped/in or out-of-pit), tailings dams (active/unshaped/uncapped), and areas requiring rehabilitation that are temporarily stabilised (i.e. managed to minimise dust generation and/or erosion).</p>
Domain	<p>An area (or areas) of the land that has been disturbed by mining and has a specific operational use (mining domain) or specific final land use (final land use domain). Land within a domain typically has similar geochemical and/or geophysical characteristics and therefore requires specific rehabilitation activities to achieve the associated final land use.</p>
Ecosystem and Land Use Development	<p>This phase of rehabilitation consists of the activities to manage maturing rehabilitation areas on a trajectory to achieving the approved rehabilitation objectives and completion criteria.</p> <p>For vegetated land uses this phase may include processes to develop characteristics of functional self-sustaining ecosystems, such as nutrient recycling, vegetation flowering and reproduction, and increasing habitat complexity, and development of a productive, self-sustaining soil profile.</p> <p>This phase of rehabilitation may include specific vegetation management strategies and maintenance such as tree thinning, supplementary plantings and weed management.</p>
Ecosystem and Land Use Establishment	<p>This phase of rehabilitation consists of the processes to establish the approved final land use following construction of the final landform.</p> <p>For vegetated land uses this rehabilitation phase includes establishing the desired vegetation community and implementing land management activities such as weed control. This phase of rehabilitation may also include habitat augmentation such as installation of nest boxes.</p>
Exploration	Has the same meaning as that term under the State Environmental Planning Policy (Mining, Petroleum Production and Extractive Industries) 2007.

WORD	DEFINITION
Final landform and rehabilitation plan	As defined in the Mining Regulation 2016.
Final land use	As defined in the Mining Regulation 2016.
Form and way	Means the form and way approved by the Secretary. Approved form and way documents are available on the Department’s website.
Growth Medium Development	<p>This phase of rehabilitation consists of activities required to establish the physical, chemical and biological components of the substrate required to establish the desired vegetation community (including short lived pioneer species).</p> <p>This phase may include spreading the prepared landform with topsoil and/or subsoil and/or soil substitutes, applying soil ameliorants to enhance the physical, chemical and biological characteristics of the growth media, and actions to minimise loss of growth media due to erosion.</p>
Habitat	Has the same meaning as that term under the <i>Biodiversity Conservation Act 2016</i> and the <i>Fisheries Management Act 1994</i> (as relevant).
Indicator	An attribute of the biophysical environment (e.g. pH, topsoil depth, biomass) that can be used to approximate the progression of a biophysical process. It can be measured and audited to demonstrate (and track) the progress of an aspect of rehabilitation towards a desired completion criterion (i.e. defined end point). It may be aligned to an established protocol and used to evaluate changes in a system.
Land	As defined in the <i>Mining Act 1992</i> .
Landform Establishment	<p>This phase of rehabilitation consists of the processes and activities required to construct the final landform.</p> <p>In addition to profiling the surface of rehabilitation areas to the approved final landform profile this phase may include works to construct surface water drainage features, encapsulate problematic materials such as tailings, and prepare a substrate with the desired physical and chemical characteristics (e.g. rock raking or ameliorating sodic materials).</p>
Large mine	As defined in the Mining Regulation 2016.
Lease holder	The holder of a mining lease.

WORD	DEFINITION
Life of mine	The timeframe of how long a mine is approved to mine, from commencement to closure.
Mine rehabilitation portal	<p>Means the NSW Resources Regulator’s online portal that lease holders must use (via a registered account) to:</p> <ul style="list-style-type: none"> ■ upload rehabilitation geographical information system (GIS) spatial data ■ develop rehabilitation GIS spatial data (using online tracing functions) ■ generate rehabilitation plans and rehabilitation statistics using the map viewer and Rehabilitation Key Performance Indicator functionalities. <p>Data submitted to the mine rehabilitation portal is collated in a centralised geodatabase for use by the NSW Resources Regulator to regulate rehabilitation performance of lease holders.</p>
Mining area	As defined in the <i>Mining Act 1992</i> .
Mining domain	A land management unit with a discrete operational function (e.g. overburden emplacement), and therefore similar geophysical characteristics, that will require specific rehabilitation treatments to achieve the final land use(s).
Mining land	As defined in the <i>Mining Act 1992</i> .
Native vegetation	Has the same meaning as that term under section 60B of the <i>Local Land Services Act 2013</i> .
Overburden	Material overlying coal or a mineral deposit.
Performance indicator	An attribute of the biophysical environment (for example pH, slope, topsoil depth, biomass) that can be used to demonstrate achievement of a rehabilitation objective. It can be measured and audited to demonstrate (and track) the progress of an aspect of rehabilitation towards a desired completion criterion, that is, a defined end point. It may be aligned to an established protocol and used to evaluate changes in a system.

WORD	DEFINITION
Phases of rehabilitation	<p>The stages and sequences of actions required to rehabilitate disturbed land to achieve the final land use. The phases of rehabilitation are:</p> <ul style="list-style-type: none"> ■ active mining ■ decommissioning ■ landform Establishment ■ growth medium development ■ ecosystem and land use establishment ■ ecosystem and land use development.
Progressive rehabilitation	<p>The progress of rehabilitation towards achieving the approved rehabilitation completion criteria. This may be described in terms of domains, phases, performance indicators and rehabilitation completion criteria.</p>
Rehabilitation Completion	<p>The final phase of rehabilitation when a rehabilitation area has achieved the approved rehabilitation objectives and rehabilitation completion criteria for the final land use. Rehabilitation areas may be classified as complete when the NSW Resources Regulator has determined in writing that the relevant rehabilitation obligations have been fulfilled following submission of <i>Form ESF2 Rehabilitation completion and/or review of rehabilitation cost estimate</i> application by the lease holder.</p>
Rehabilitation Completion criteria	<p>As defined in the Mining Regulation 2016.</p>
Rehabilitation cost estimate	<p>As defined in the Mining Regulation 2016.</p>
Rehabilitation management plan	<p>As defined in the Mining Regulation 2016.</p>
Rehabilitation objectives	<p>As defined in the Mining Regulation 2016.</p>
Rehabilitation risk assessment	<p>As defined in the Mining Regulation 2016.</p>
Rehabilitation schedule	<p>The defined timeframes for progressive rehabilitation set out in the forward program.</p>

WORD	DEFINITION
Relevant stakeholders	<p>Means any persons or bodies who may be affected by the mining operations, including rehabilitation, carried out on the lease land, and includes:</p> <ul style="list-style-type: none"> ■ the relevant development consent authority ■ the local council ■ the relevant landholder(s) ■ community consultative committee (if required under the development consent) or equivalent consultative group ■ affected land holder(s) ■ government agencies relevant to the final land use ■ affected infrastructure authorities (electricity, telecommunications, water, pipeline, road, rail authorities) ■ local Aboriginal communities, and ■ any other person or body determined by the Minister to be a relevant stakeholder in relation to a mining lease.
Risk	The effect of uncertainty on objectives. It is measured in terms of consequences and likelihood (AS/NZS ISO 31000:2009).
Secretary	The Secretary of the Department.
Security deposit	An amount that a mining lease holder is required to provide and maintain under a mining lease condition, to secure funding for the fulfilment of obligations under the lease (including obligations that may arise in the future).
Surface disturbance	Includes activities that disturb the surface of the mining area, including mining operations, ancillary mining activities and exploration.
Tailings	A combination of the fine-grained solid material remaining after the recoverable metals and minerals have been extracted from the mined ore, and any process water ² .
Waste	Has the same meaning as that term under the <i>Protection of the Environment Operations Act 1997</i> .

² Commonwealth of Australia (DITR), 2007. *Tailings Management*.

Attachment 3 – Plans

Plan 2A.pdf

Plan 2B.pdf

Plan 2C.pdf

Forward Program (LARGE MINE) v2.1



ML1818

Avoca Tank Mine

North East Mine

ML1383

REFERENCE


-  Project Approval Boundary
-  Mineral Authority Boundary

Mine Name	North East Mine / Avoca Tank Mine
Plan Name	Plan 2A Mining and Rehabilitation - Year 1
Anticipated Year of Relinquishment	2034
Date Plan Created	27 August 2024
Data Theme Submission ID Numbers	8439

SCALE 1:30 000 (A3)



Contour Source: Department of Finance, Services and Innovation



REFERENCE

-  Project Approval Boundary
-  Mineral Authority Boundary

Mine Name	North East Mine / Avoca Tank Mine
Plan Name	Plan 2B Mining and Rehabilitation - Year 2
Anticipated Year of Relinquishment	2034
Date Plan Created	27 August 2024
Data Theme Submission ID Numbers	8440

SCALE 1:30 000 (A3)



Contour Source: Department of Finance, Services and Innovation



REFERENCE

-  Project Approval Boundary
-  Mineral Authority Boundary

Mine Name	North East Mine / Avoca Tank Mine
Plan Name	Plan 2C Mining and Rehabilitation - Year 3
Anticipated Year of Relinquishment	2034
Date Plan Created	27 August 2024
Data Theme Submission ID Numbers	8441

SCALE 1:30 000 (A3)



Contour Source: Department of Finance, Services and Innovation